



THE STATUS OF THE LHC AND FUTURE PROJECTS AT CERN

Emmanuel Tsesmelis

Directorate Office, CERN &

Visiting Lecturer, JAI

The University of Oxford 13 March 2009

Table of Contents

Status of the LHC

- The LHC Accelerator
- Commissioning with Beam
- Sector 3-4 Incident
- Commissioning the Physics Programme
- Physics Run 2009-2010

Future Projects at CERN

- ATLAS/CMS Interaction Regions
- LHC Pre-Accelerators






THE LHC ACCELERATOR



Accelerato




John Adams Draitive

To Accelerator
Solence

LHC Accelerator & Experiments



LHC LAY-OUT



- The LHC is a two-ring superconducting proton-proton collider made of eight 3.3 km long arcs separated by 528 m Long Straight Sections.
- While the 8 eight arcs are nearly identical, the 4 straight sections are very different.

Momentum at collision	7 TeV/c
Momentum at injection	450 GeV/c
Dipole field at 7 TeV	8.33 Tesla
Circumference	26658 m
Stored energy magnets	9.4 GJ

Luminosity	10 ³⁴ cn	n ⁻² s ⁻¹	
Number of bunches	2808	2808	
Particles per bunch	1.1 · 10	1.1· 10 ¹¹	
DC beam current	0.56	Α	
Stored energy per beam	360	MJ	

Normalised emittance	3.75	μm
Beam size at IP / 7 TeV	15.9	μm
Beam size in arcs (rms)	300	μm

Arcs: Counter-rotating proton beams in twoin-one magnets

Magnet coil inner diameter 56 mm

Distance between beams 194 mm

High beam energy in LEP tunnel superconducting NbTi magnets at 1.9 K


High luminosity at 7 TeV very high energy stored in the beam

25 ns bunch-spacing

Beam power concentrated in small area

Limited investment small aperture for beams

LHC Main Bending Cryodipole




8.33 T nominal field

11850 A nominal current



Magnet Interconnections



DIPOLE-DIPOLE INTERCONNECT BEFORE FINAL CLOSURE

Consist of several operations:

- TIG welding of cryogenic channels (~50 000 welds)
- Induction soldering of main superconducting cables (~ 10 000 joints)
- Ultrasonic welding of auxiliary superconducting cables (~ 20 000 welds)
- Mechanical assembly of various elements
- □ Installation multi-layer insulation (~ 200 000 m²)


All interconnections completed in November 2007






COMMISSIONING WITH BEAM

LHC Injection




Preparing the LHC Synchronisation Tests


TT40 - Sept/Oct 2003




TI8 - Sept 2004



TI2 - 2007




Synchronisation of LHC Clockwise Beam



The yellow spot shows a bunch of a few particles arriving at Point 3 of the LHC ring

Injected Beam to LHCb

22-24 August 2008




3rd Synchronisation Test




CMS Calorimeter and Muon System Recording Beam Dump on TCT in 5L

10 September 2008




First Circulating Beam ATLAS

Beam 1




First Circulating Beam CMS


Event showing beam halo muon from Beam-2 through CMS




Circulating Beam



Few 100 Turns




Dump Dilution Sweep



Circulating Beam

No RF


Debunching in 25*10 Turns (~25 ms.)



Beam Capture


First attempt to capture

At wrong injection phase



Courtesy E. Ciapala


Beam Capture




Capture with corrected injection phase

Beam Capture

Capture with optimum injection phasing and correct reference



LHC Longitudinal Bunch Profile







SECTOR 3-4 INCIDENT



Situation on 10th September



7 out of 8 sectors fully commissioned for
 5 TeV operation and 1 sector (3-4)
 commissioned up to 4 TeV.



Interim Summary Report on the analysis of the 19th September 2008 incident at the LHC



Incident during powering

The magnet circuits in the seven other sectors of the LHC had been fully commissioned to their nominal currents (corresponding to beam energy of 5.5 TeV) before the first beam injection on 10 September 2008. For the main dipole circuit, this meant a powering in stages up to a current of 9.3 kA. The dipole circuit of sector 3-4, the last one to be commissioned, had only been powered to 7 kA prior to 10 September 2008. After the successful injection and circulation of the first beams at 0.45 TeV, commissioning of this sector up to the 5.5 TeV beam energy level was resumed as planned and according to established procedures.

On 19 September 2008 morning, the current was being ramped up to 9.3 kA in the main dipole circuit at the nominal rate of 10 A/s, when at a value of 8.7 kA, a resistive zone developed in the electrical bus in the region between dipole C24 and quadrupole Q24. The first evidence was the appearance of a voltage of 300 mV detected in the circuit above the noise level: the time was 11:18:36 CEST. No resistive voltage appeared on the dipoles of the circuit, individually equipped with quench detectors with a detection sensitivity of 100 mV each, so that the quench of any magnet can be excluded as initial event. After 0.39 s, the resistive voltage had grown to 1 V and the power converter, unable to maintain the current ramp, tripped off at 0.46 s (slow discharge mode). The current started to decrease in the circuit and at 0.86 s, the energy discharge switch opened, inserting dump resistors in the circuit to produce a fast power abort. In this sequence of events, the quench detection, power converter and energy discharge systems behaved as expected.



Interim Summary Report on the analysis of the 19th September 2008 incident at the LHC



Sequence of events and consequences

Within the first second, an electrical arc developed and punctured the helium enclosure, leading to release of helium into the insulation vacuum of the cryostat.

The spring-loaded relief discs on the vacuum enclosure opened when the pressure exceeded atmospheric, thus relieving the helium to the tunnel. They were however unable to contain the pressure rise below the nominal 0.15 MPa absolute in the vacuum enclosures of subsector 23-25, thus resulting in large pressure forces acting on the vacuum barriers separating neighboring subsectors, which most probably damaged them. These forces displaced dipoles in the subsectors affected from their cold internal supports, and knocked the Short Straight Section cryostats housing the quadrupoles and vacuum barriers from their external support jacks at positions Q23, Q27 and Q31, in some locations breaking their anchors in the concrete floor of the tunnel. The displacement of the Short Straight Section cryostats also damaged the "jumper" connections to the cryogenic distribution line, but without rupture of the transverse vacuum barriers equipping these jumper connections, so that the insulation vacuum in the cryogenic line did not degrade.

Electrical arc between C24 and Q24








US testing 13 kA splices

US inspection of defective inter-pole splice in MB 2334 has confirmed the US test to be a very useful QC tool.





Courtesy C. Scheurlein

Inventory of magnets in D-zone

- 15 SSS (MQ)
 - 1 not removed (Q19)
 - 14 removed
 - 8 cold mass revamped (old CM, partial decryostating for cleaning and careful inspection of supports and other components)
 - 6 new CMs
 - In this breakdown there is consideration about timing (SSS cryostating tales long time; variants problems).

42 Dipoles (MBs)

- 3 not removed (A209,B20,C20)
- 39 removed
 - 9 Re-used (old CM, no decryostating -except one?)
 - 30 new CMs
 - New cold masses are much faster to prepare than rescuing doubtful dipoles)


CURRENT ESTIMATE: ALL MAGNETS TO TUNNEL IN WEEK 15 (April 10)

LHC Improvements

- Probability reduction for "s34-like incident"
 - New QPS and QDS will be deployed now on whole machine (incl. symm quench detection)
- Mitigation of damage in case of new incident
 - SSS relief valves DN100 on all arcs (install now)
 - Dipole relief valves DN200 (install now on warmedup sectors, other sectors in 2010/2011)
- Calorimetric (precision of 20 n Ω) and electrical measurement of resistance (precision of 1 n Ω).

Training during HWC










COMMISSIONING THE PHYSICS PROGRAMME



Integrated luminosity × cross section versus energy

- What integrated luminosity should the LHC accumulate to overtake the Tevatron, which aims for 9 fb⁻¹ by 2010?
- What is the minimum amount of data at given energy that is needed to make the 2009 physics run useful? (assuming CM energy 8 < s^{1/2} < 10 TeV)</p>

Physics of ATLAS/CMS

Discovery Channels

- Higgs
- W', Z'
- SUSY
- Exotic particles

Try to express these as:


- Luminosity needed to make a better (exclusion) measurement than Tevatron.
- 2. Luminosity needed to make a discovery.

Standard Model Channels

- W, Z
- top
- QCD

An excellent understanding of these is an essential step toward Discoveries.

Tevatron




Projected
Integrated
Luminosity


How much by end of 2010?

Higgs 95% CL at LHC H → weak bosons

Combined H→WW + H→ZZ: lumi for 95% CL



- $\blacksquare \quad \overline{\text{Energy s}^{1/2} \quad 14 \quad \rightarrow \quad 10 \quad \rightarrow \quad 6 \quad \overline{\text{TeV}}}$
- Lumi needed $0.1 \rightarrow 0.2 \rightarrow 0.6$ fb⁻¹




Compare sensitivity to Tevatron with 8 fb⁻¹ (only H \rightarrow WW \rightarrow IvIv)

Massive loss of sensitivity below 6 TeV

To challenge Tevatron with $s^{1/2} = 8-10$ TeV, LHC needs $\sim 200-300$ pb⁻¹ g.d.

Higgs 5_o Discovery



 5σ discovery for m_H ~160 GeV is possible with $s^{1/2} = 8-10$ TeV and ~1fb⁻¹ g.d.

Luminosities at $s^{1/2} = 10$ TeV

$$f k_b N^2 \gamma$$

$$L = \frac{1}{4\pi} \epsilon_N \beta^*$$

$$\beta^* = 3 m.$$

$$N=10^{11} \text{ protons/bunch}$$

Assume (somewhat arbitrarily) a "Hübner factor" of 0.2




$$k_b = 156$$
 \Rightarrow 6×10^{31} cm⁻² s⁻¹


 \Rightarrow ~ 1 pb⁻¹ / day

$$k_b = 1404$$
 \Rightarrow 5×10^{32} cm⁻² s⁻¹

 \Rightarrow ~ 8 pb⁻¹ / day







Note: Tevatron is cruising at $\sim 3\times 10^{32}$ cm⁻² s⁻¹ (8 pb⁻¹/day, 2 fb⁻¹ / year) \Rightarrow LHC needs high energy!

ATLAS/CMS Discovery Channels

- Typically, with 50-100 pb⁻¹ good data at 10-8 TeV ⇒ many new limits set on hypothetical particles (some more stringent than Tevatron), or even discoveries possible!
- With 200-300 pb⁻¹ g.d. at 10-8 TeV \Rightarrow start competing with Tevatron for Higgs masses around 160 GeV
- With 1 fb⁻¹ g.d. at 10 TeV \Rightarrow find Higgs if around 160 GeV mass
- The higher the energy, the faster it goes...
- Note: below ~20-40 pb⁻¹ g.d. at 10-8 TeV, or at any lower energy, one would probably start talking about an "engineering run"

LHCb Running Conditions

- B cross section does not vary as drastically as for high-mass objects.
 - Thus, the request to go to highest possible energy is milder.
- Need 0.3-0.5 fb⁻¹ at $s^{1/2} \ge 8$ TeV to surpass Tevatron in B_s physics.
- Need at least 5 pb⁻¹ at $s^{1/2} \ge 4$ TeV to collect good sample of J/psi.

ALICE and pp Running

- ALICE not as strongly interested as ATLAS/CMS in reaching the highest possible energy for pp.
- What about $s^{1/2} = 5.5 \text{ TeV}$? (the *NN* equivalent in PbPb @ 14TeV)
 - Not so crucial at this stage, but yes, would request to choose E=2.75 TeV if a beam energy between 2 and 3 TeV was being considered.
- Will collect data at $\sim 10^{29}$ cm⁻² s⁻¹ (opt) or 3×10^{30} cm⁻² s⁻¹ (max)






PHYSICS RUN 2009-2010

The Preferred Scenario

Start the LHC as soon as possible and run for one year




Scenario with greatest flexibility

maintenance

- Can adapt LHC goals to evolving circumstances
 - Increase 8 => 12 TeV in the course of 2010?
- Heavy -ion run at the end of 2010
 - adjust end date (start of shutdown)


Shutdown 08-09



- ্ট Intermediate cool-down & QRL warmup (Stand Alone)


- Flushing & ELQA at warm
- Cool-down
- ☼ Cold check-out

Schedule with Running in Winter Months



THE LHC UPGRADE

Peak Luminosity



Phase-1 Upgrade Interaction Region


Goal of the upgrade:

Enable focusing of the beams to $\beta^*=0.25$ m in IP1 and IP5, and reliable operation of the LHC at 2 to 3 10^{34} cm⁻²s⁻¹ on the horizon of the physics run in 2013.


Scope of the Project:

- 1. Upgrade of ATLAS and CMS interaction regions. The interfaces between the LHC and the experiments remain unchanged.
- 2. The cryogenic cooling capacity and other infrastructure in IR1 and IR5 remain unchanged and will be used to the full potential.
- 3. Replace the present triplets with wide aperture quadrupoles based on the LHC dipole (Nb-Ti) cables cooled at 1.9 K.
- 4. Upgrade the D1 separation dipoles, TAS and other beam-line equipment so as to be compatible with the inner triplets.
- 5. Modify matching sections to improve optics flexibility and machine protection, and introduce other equipment relevant for luminosity increase to the extent of available resources.

Phase-1 Upgrade Interaction Region



Large-aperture Quadrupoles




Half aperture = 60 mm compared to 35 mm now

•	Coil aperture	120 mm
•	Gradient	120 T/m
•	Operating temp	1.9 K
•	Current	13 kA
•	Inductance	5 mH/m
•	Yoke ID	260 mm
•	Yoke OD	550 mm

- LHC cables 01 and 02
 - Enhanced cable polyimide insulation
 Self-supporting collars
 Single piece yoke
 Welded-shell cold mass

Present and Future Injectors



Proton flux / Beam power

LP-SPL: Low Power -Superconducting Proton Linac (4-5 GeV)

PS2: High Energy PS (~ 5 to 50 GeV – 0.3 Hz)

SPS+: Superconducting SPS (50 to1000 GeV)

SLHC: "Superluminosity" LHC (up to 10³⁵ cm⁻²s⁻¹)

DLHC: "Double energy" LHC

(1 to ~14 TeV)



Pre-accelerator Upgrade


Main Performance Limitation:

Incoherent space charge tune spreads ΔQ_{SC} at injection in the PSB (50 MeV) and PS (1.4 GeV) because of the required beam brightness N/ε^* .

$$\Delta Q_{SC} \propto \frac{N_b}{\varepsilon_{X,Y}} \cdot \frac{R}{\beta \gamma^2}$$

- ⇒ need to increase the injection energy in the synchrotrons
- Increase injection energy in the PSB from 50 to 160 MeV kinetic
- Increase injection energy in the SPS from 25 to 50 GeV kinetic
- Design the PS successor (PS2) with an acceptable space charge effect for the maximum beam envisaged for SLHC: => injection energy of 4 GeV

Upgraded Pre-accelerators



Timetable

	Interaction Region	Pre-accelerators
2008	IR upgrade design + Collimation Upgrade	Start design of SPL/PS2 Start construction of Linac4
2011		Detailed project proposals for SPL/PS2 (TDR + cost estimates)
2012		Start of construction of SPL/PS2 Commissioning Linac4
2013	Commissioning of IR upgrade	Beam from Linac4/PSB
2017		Commissioning of SPL/PS2

LHC Upgrade Phase-2

early separation (ES)

```
\beta^*~0.1 m, 25 ns, N_b=1.7x10<sup>11</sup>, detector embedded dipoles
```

full crab crossing (FCC)

```
\beta^*~0.1 m, 25 ns, N_b=1.7x10<sup>11</sup>, local and/or global crab cavities
```


large Piwinski angle (LPA)


```
\beta^*~0.25 m, 50 ns, N_b=4.9x10<sup>11</sup>, "flat" intense bunches
```

low emittance (LE)

```
\beta^*~0.1 m, 25 ns, \gamma \varepsilon~1-2 \mum, N_b=1.7x10<sup>11</sup>
```


Phase-2 IR Layouts





- early-separation dipoles in side detectors, crab cavities
 - \rightarrow hardware inside ATLAS & CMS detectors, first hadron crab cavities; off- $\!\delta$ $\!\beta$

- crab cavities with 60% higher voltage
 - \rightarrow first hadron crab cavities, off- δ β -beat



low emittance (LE) R. Garoby stronger triplet magnets

- long-range beam-beam wire compensation
- \rightarrow novel operating regime for hadron colliders, beam generation

- smaller transverse emittance
 - \rightarrow constraint on new injectors, off- δ β -beat

parameter	symbol	nominal	ultimate	ES	FCC	LE	LPA
transverse emittance	ε [μm]	3.75	3.75	3.75	3.75	1.0	3.75
protons per bunch	$N_b [10^{11}]$	1.15	1.7	1.7	1.7	1.7	4.9
bunch spacing	Δt [ns]	25	25	25	25	25	50
beam current	I [A]	0.58	0.86	0.86	0.86	086	1.22
longitudinal profile		Gauss	Gauss	Gauss	Gauss	Gauss	Flat
rms bunch length	σ_{z} [cm]	7.55	7.55	7.55	7.55	7.55	11.8
beta* at IP1&5	β* [m]	0.55	0.5	0.08	0.08	0.1	0.25
full crossing angle	θ_{c} [µrad]	285	315	0	0	311	381
Piwinski parameter	$\phi = \theta_c \sigma_z / (2 * \sigma_x *)$	0.64	0.75	0	0	3.2	2.0
geometric reduction		1.0	1.0	0.86	0.86	0.30	0.99
peak luminosity	$L [10^{34} \text{ cm}^{-2}\text{s}^{-1}]$	1	2.3	15.5	15.5	16.3	10.7
peak events per #ing		19	44	294	294	309	403
initial lumi lifetime	$\tau_{_{ m L}}[h]$	22	14	2.2	2.2	2.0	4.5
effective luminosity	$L_{eff}[10^{34}~{ m cm}^{-2}{ m s}^{-1}]$	0.46	0.91	2.4	2.4	2.5	2.5
(T _{turnaround} =10 h)	T _{run,opt} [h]	21.2	17.0	6.6	6.6	6.4	9.5
effective luminosity	$L_{eff}[10^{34}~{ m cm}^{-2}{ m s}^{-1}]$	0.56	1.15	3.6	3.6	3.7	3.5
$(T_{turnaround} = 5 h)$	T _{run,opt} [h]	15.0	12.0	4.6	4.6	4.5	6.7
e-c heat SEY=1.4(1.3)	P [W/m]	1.1 (0.4)	1.04(0.6)	1.0 (0.6)	1.0 (0.6)	1.0 (0.6)	0.4 (0.1)
SR heat load 4.6-20 K	P _{SR} [W/m]	0.17	0.25	0.25	0.25	0.25	0.36
image current heat	P _{IC} [W/m]	0.15	0.33	0.33	0.33	0.33	0.78
gas-s. 100 h (10 h) $\tau_{\rm b}$	P _{gas} [W/m]	0.04 (0.4)	0.06 (0.6)	0.06 (0.56)	0.06 (0.56)	0.06 (0.56)	0.09 (0.9)
extent luminous region	σ_{l} [cm]	4.5	4.3	3.7	3.7	1.5	5.3
comment		nominal	ultimate	D0 + crab	crab		wire comp.

Summary and Conclusions

- Repair of the Sector 3-4 and consolidation/improvements to the machine are well-underway.
 - The technical parameters of the LHC are beyond precedent and the energy stored in the superconducting magnets is huge.
- It is expected that injection into the LHC will take place at the end of September this year, with collisions following in late October.
 - LHC will then run through to autumn 2010.
 - Schedule also permits possible collisions of Pb ions in 2010.
- The experiments are expected to be ready with their set-ups for the re-start of LHC operation in 2009.
- The LHC will be the most powerful instrument ever built to investigate properties of particles and the physics results from the LHC will determine the future course of high energy physics.
 - Projects already underway to improve the performance of the LHC