



From Linear Collider to European XFEL (and back again)



Nick Walker - DESY
Oxford, 13th February, 2017

Introduction


- A history of the (I)LC (over 20 years ..and counting)
- A history of TESLA 1.3 GHz SRF technology
- Status (and results) of the European XFEL
 - extrapolation to ILC
- ILC —what's next?

So why a Linear Collider?

- Synchrotron Radiation

$$\Delta E / rev = \frac{C_\gamma E^4}{\rho}$$

- Cost “optimum” scaling
 - Cost $\sim E^2$
 - Radius $\sim E^2$
 - MWatt $\sim E^2$



One can argue about where the cross-over point is, but the ultimate future of e^+e^- energy-frontier colliders is linear (or not at all).

An Old Idea


A Possible Apparatus for Electron-Clashing Experiments (*).

M. Tigner

Laboratory of Nuclear Studies. Cornell University - Ithaca, N.Y.

Nuovo Cimento 37 (**1965**) 1228

“While the storage ring concept for providing clashing-beam experiments is very elegant in concept it seems worth-while at the present juncture to investigate other methods which, while less elegant and superficially more complex may prove more tractable.”



The real start of the story



Burt Richter





SLAC Linear Collider (SLC)

$E_{\text{cm}} \sim 90 \text{ GeV}$

1989-1998

A proof of principle



Evolution

1994

Technology Review
Committee (TRC) I

TESLA (DESY)	1.3 GHz
SBLC (DESY)	3.0 GHz
JLC-S (KEK)	2.8 GHz
JLC-C (KEK)	5.7 GHz
JLC-X (KEK)	11.4 GHz
NLC (SLAC)	11.4 GHz
VLEPP (IHEP)	14.0 GHz
CLIC (CERN)	30 GHz

Evolution

1994

Technology Review
Committee (TRC) I

TESLA (DESY) 1.3 GHz

SBLC (DESY) 3.0 GHz

JLC-S (KEK) 2.8 GHz

JLC-C (KEK) 5.7 GHz

JLC-X (KEK) 11.4 GHz

NLC (SLAC) 11.4 GHz

VLEPP (IHEP) 14.0 GHz

CLIC (CERN) 30 GHz

2003

Technology Review
Committee (TRC) II

TESLA (DESY) 1.3 GHz

JLC-C (KEK) 5.7 GHz


JLC-X (KEK) 11.4 GHz

NLC (SLAC) 11.4 GHz


CLIC (CERN) 30 GHz



Evolution



Evolution



Why SRF?




- Low-loss cavities
 - High RF → Beam-power efficiency
 - Lower operational costs
- Ease of RF power generation
 - low frequency (1.3 GHz)
 - Long pulse / fill time (1ms / 0.6ms)
 - Low peak power (≤ 10 MW)
- Emittance preservation
 - large cavity iris (low frequency)
 - low transverse and longitudinal wakefields
 - loose alignment tolerances

Why SRF?



- Low-loss cavities
 - High RF→Beam-power efficiency
 - Lower operational costs
- Ease of RF power generation
 - low frequency (1.3 GHz)
 - Long pulse / fill time (1ms / 0.6ms)
 - Low peak power (≤ 10 MW)
- Emittance preservation
 - large cavity iris (low frequency)
 - low transverse and longitudinal wakefields
 - loose alignment tolerances




Why SRF?

“The construction of the superconducting XFEL free electron laser will provide prototypes and test many aspects of the linac.”

ITRP final report executive summary

ILC time line

- Pre Global Design Effort
 - 1992 TESLA starts
 - 2002 German BMBF XFEL decision
 - 2004 ITRP decision
 - 2009 XFEL construction begins
- Since 2005: GDE (B. Barish)
 - 2005-2007 Reference Design Report and cost estimate
 - 2008-2012 Technical Design Phase
 - 2012 TDR and updated cost estimate
- 2013-
Linear Collider Collaboration (LCC, L. Evans)
towards project realisation in Japan.




TESLA Technology



- 1.3 GHz solid niobium nine-cell resonator (cavity)
- 1990's goal: reduction in \$/MeV by a factor of 20
 - Factor 5 in gradient \rightarrow 25 MV/m
 - Factor 4 from cryostat integration

The Quest for High Gradient



courtesy Rongli Geng

The path to high performance

- Control of niobium material (high purity)
- Mechanical construction in a clean environment
 - electron-beam welding (EBW)
- Preparing RF (inner) surface ultra-clean mirror surface
 - electro-polishing (EP)
- Removing hydrogen from the surface layer
 - 800 deg C bake
- Removing surface contamination
 - alcohol and/or detergent rinsing
 - 100-150 bar high-pressure rinsing (HPR)



High gradient

High Q_0

Low Field
Emission
(dark current)




European XFEL



100 cryomodules
→ 800 1.3 GHz 9-cell cavities
 $\langle E_{\text{acc}} \rangle = 23.6 \text{ MV/m}$
10 Hz rep. rate
1.4 ms RF pulse (750 us+650 us)



The European XFEL

Built by Research Institutes from 12 European Nations




Some specifications

- Photon energy 0.3 - 24 keV
- Pulse duration ~ 10 - 100 fs
- Pulse energy few mJ
- Superconducting linac 17.5 GeV
- 10 Hz (27 000 b/s)
- 5 beam lines / 10 instruments
 - Start version with 3 beam lines and 6 instruments
- Several extensions possible:
 - More undulators
 - More instruments
 -
 - Variable polarization
 - Self-Seeding
 - CW operation



XFEL cryomodule production




Achieving testing rates



- AMTF @ DESY
 - Accelerator Module Test Facility
 - Purpose build infrastructure
- Vertical cavity testing
 - Two independent cryostats
 - six inserts, each carrying 4 cavities
 - Test cycle ~3 days
- Module testing
 - Three parallel test benches
 - Module test 21 → 14 days
 - including cool down and warm up.

Operated by staff from IFJ-PAN (Cracow)

Achieving testing rates



Two
independent
vertical
cryostats

Six inserts,
each taking 4
cavities

Average rate during main production period ~10 cavity tests per week
Up to 15 peak achieved

courtesy
Olivier
Napoly

Clean
rooms

Assembly
halls

Offices

Warehouse

XFEL Village

Bldg 126 North
40x11 m²


Bldg 126 South
30x17 m²

Bldg 124 North
25x15 m²

Bldg 124 North
192 m²

Court
Yard

courtesy
Olivier
Napoly




the XFEL Village

Module integration route

7 weeks per module
7 work stations (parallel)
→ 1 module / week

courtesy
Olivier
Napoly




Module integration route

7 weeks per module
7 work stations (parallel)
→ 1 module / week

12 February 2016

Module assembly rate

- 5 day throughput was reached **mid-October 2014** with **XM15**
⇒ the design of the Assembly Infrastructure was sound



4-day throughput was reached in **January 2015** with **XM25**

This 'accelerated' rate is needed to close the XFEL tunnel mid-2016:

- XM80 to be delivered at the end of December 2015
- XM100 to be delivered at the end of April 2016

courtesy
Olivier
Napoly

XFEL performance results

So how well did we do?

- gradient
- Q_0



- Cavity vertical test (vendor acceptance test)
- Module performance test

As Received Maximum Gradient in the VT


5

typical individual error: 10%


BD: breakdown (quench) - FE: field emission - PWR: power limited




		Max
Average	MV/m	31.4
RMS	MV/m	6.8
Median (50%)	MV/m	32.5
Yield ≥ 20 MV/m		92%
Yield ≥ 26 MV/m		85%



As Received Usable Gradient in the VT




typical individual error: 10%



Include operations spec



- $Q_0 \geq 1 \times 10^{10}$
- FE threshold (X-ray)

→ Usable Gradient




		Max	Usable
Average	MV/m	31.4	27.7
RMS	MV/m	6.8	7.2
Median (50%)	MV/m	32.5	28.7
Yield ≥ 20 MV/m		92%	86%
Yield ≥ 26 MV/m		85%	66%

Usable gradient: limiting effects





- Q_0 dominates at higher gradients (high-gradient Q-slope)
- Field Emission (FE) dominates <24 MV/m
- Quench (BD) not dominant –mostly higher gradients

Recovering low performance cavities




- $E_{\text{usable}} < 20 \text{ MV/m}$ rejected
 - Approx. 15% cavities
- Sent for surface retreatment
 - Mostly High Pressure Rinse (HPR)
 - Small fraction Buffered Chemical Polishing (BCP) and/or “grinding”




		Max	Usable
Average	MV/m	31.4	27.7
RMS	MV/m	6.8	7.2
Median (50%)	MV/m	32.5	28.7
Yield $\geq 20 \text{ MV/m}$		92%	86%
Yield $\geq 26 \text{ MV/m}$		85%	66%


Number of retreatments after the 1st vertical test



- Approx. 22% of cavities had ≥ 1 retreatment
 - ~15% performance-driven
 - ~7% due to vacuum- and mechanical-related problems (mostly HPR)
- 5% had 2 or more retreatments.
 - including both chemical and mechanical (grinding)




Final performance (sent for module assembly)




■ $\langle E_{\text{usable}} \rangle = 29.8 \pm 5.1 \text{ MV/m}$

impact of
retreatment



Cryomodule assembly at CEA Saclay



Always a risk when cavity vacuum is broken
(even in the clean room)




Comparing VT with module test performance

	VT	MT	
Maximum gradient	No administrative limit	limited to 31 MV/m	<i>True impact unknown (but can set an upper limit)</i>
Field Emission (X-Ray)	Two monitors above and below cryostat	Two monitors upstream and downstream of cryomodule axis	<i>Different geometry / calibration makes exact comparison difficult</i>
Q_0	RF measurement	~1 hour 2K cryoload measurement with all cavities on resonance	<i>No Q_0 limit taken in MT definition of usable gradient.</i>
General	CW measurement	Pulse RF measurement (10% duty cycle)	<i>Systematic errors and uncertainties</i>



Comparing VT with module test performance

	VT	MT	
Maximum gradient	No administrative limit	limited to 31 MV/m	<i>True impact unknown (but can set an upper limit)</i>
Field Emission (X-Ray)	Two monitors above and below cryostat	Two monitors upstream and	<i>Different geometry / calibration makes comparison difficult</i>
Q_0		measurement with all cavities on resonance	<i>The Q_0 limit taken in MT definition of usable gradient.</i>
General	CW measurement	Pulse RF measurement (10% duty cycle)	<i>Systematic errors and uncertainties</i>

when making comparisons,



Cryomodule average gradient performance




VT capped at 31 MV/m for
fair comparison


	N _{cavs}	Average	RMS
VT	815	28.3 MV/m	3.5
CM	815	27.5 MV/m	4.8

**~3% difference measured
this way**



Degradation matrix



Degradation defined as $\geq 20\%$ (red)




best place to be
a happy cavity in
a cryomodule



- <5%
- <10%
- <15%
- <20%
- $\geq 20\%$


Cryomodule performance (AMTF module test)



cryomodules installed in linac


Average (blue line) is good but spread within modules is still quite large
→ “Fine tuning” of waveguide distribution to maximise energy gain.

Impact of Waveguide Distribution (WD) system (Installed Gradient)




courtesy V. Katelev

- 1 10-MW klystron drives four modules (32 cavities)
- WD for cryomodules tailored for MT results
 - maximising voltage
 - up to 3dB difference between cavity pairs
- Allow up to 3dB split between adjacent cryomodule pairs
- Equal power output from two klystron arms





Impact of Waveguide Distribution (WD) system (Installed Gradient)

24



courtesy V. Katelev


- 1 10-MW klystron drives (32 cavities)
- WD for cryomodules tail results
 - maximising voltage
 - up to 3dB difference between cavity pairs
- Allow up to 3dB split between adjacent cryomodule pairs
- Equal power output from two klystron arms



see THPLR067 Choroba, Katalev, Apostolov

Projected installed energy profile

$$E_{\text{max}} \sim 20 \text{ GeV}$$




17.5 GeV 14% margin at
17.5 GeV

23.6 MV/m

4.3 MW

First Cooldown of XFEL Linac (300K to 4K)

44



10.12.2016



24.12.2016


■ **No Cold Leaks!!!**

XFEL cryogenics


- 2K operation achieved on 6.01.2017 ($P = 30.6$ mbar)
- He pressure stability $\pm 0.3\%$ (spec. $\pm 1\%$)
- Still “learning” new Cold Compressors (CC)
 - Not yet operating at design capacity
 - Reliability issues
- Operations issues
 - relatively high ‘dynamic load’ (RF - scales as G^2)
 - commissioning at 1 Hz to keep dynamic load low
 - Not yet “challenged”

XFEL commissioning


- Injector commissioning (130 MeV) 12.2016 ✓
- L1 (A2) commissioning (600 MeV) 01.02.2016 ✓
- L2 (A2/3/4) commissioning (2.4 GeV) 15.02.2016 ✓
- L3 (A6-25) commissioning (\rightarrow 17.5 GeV) ongoing (sched. until 15.04.2017)



From XFEL to ILC?



So how close are we?



Gradient?
Cost??

ILC cavity specs

	ILC		XFEL (spec)	
	G (MV/m)	Q ₀	G (MV/m)	Q ₀
Vertical Test	35.0	5×10 ⁹	26.0	10 ¹⁰
Installed	31.5	10 ¹⁰	23.6	10 ¹⁰

ILC cavity specs

	ILC		XFEL (spec)	
	G (MV/m)	Q_0	G (MV/m)	Q_0
Vertical Test	35.0	5×10^9	26.0	10^{10}
Installed	31.5	10^{10}	23.6	10^{10}

ILC TDR assumed $\pm 20\%$ gradient spread ($28 \leq G \leq 42$ MV/m)


	Yield ≥ 28 MV/m	$\langle G \rangle \geq 28$ MV/m
As received (1st pass)	75%	35 MV/m
After 25% retreated (2nd pass)	90%	35 MV/m

$\Rightarrow 1.25$ VT per cavity

cost model

Test results by Vendor (MAX GRADIENT)


“As received” test




Clearly see difference between RI (final EP) and EZ (flash-BCP)


ILC TDR recipe (RI, final EP)

	RI	EZ	Total
Tests	375	368	743
G_{AVG} (MV/m)	33.	29.8	31.4
G_{RMS} (MV/m)	6.6	6.6	6.8
yield @ 20MV/m	94%	89%	92%
yield @ 26MV/m	90%	80%	85%
yield @ 28MV/m	86%	73%	79%




Retreatment model (monte carlo)





RI results only (ILC recipe)


		ILC TDR (assumed)	XFEL	
			max	usable
First-pass	Yield >28 MV/m Average >28 MV/m	75% 35 MV/m	85% 35.2 MV/m	63% 33.5 MV/m
First+Second pass	Yield >28 MV/m Average >28 MV/m	90% 35 MV/m	94% 35.0 MV/m	82% 33.4 MV/m
First+Second+third pass	Yield >28 MV/m Average >28 MV/m	- -		91% 33.4 MV/m




but close!

More re-treatments - but mostly only HPR

Number of average tests/cavity increases from 1.25 to 1.55 (1st+2nd) or
20% over-production or additional re-treat/test cycles



XFEL cryomodule cost



ILC TDR ~1.3 M€ (2012)

Module cost: XFEL to ILC

XFEL cost

2.13 M€

100 modules in 2 years

1 module / week

100% testing

Extrapolated ILC
European IKC based on 640
module production in 7 years

1.55 M€

(20% uncertainty)

640 modules in 7 years

2 module / week

100% testing

- reuse of existing infrastructure
- reduced infrastructure cost per module
- assumed 95% slope learning curve (8-12%)
- two vendor model

ILC TDR

1.3 M€

(28% uncertainty)

1860 modules in 3 years

12 module / week

33% testing


- reduced infrastructure cost per module
- assumed 95% slope learning curve (8-12%)
- two vendor model
- purpose-built infrastructure for high production rates

part of study for
“European Action Plan”
(work in progress)

SRF cost reduction R&D



Optimal Linac Gradient




Plot courtesy
Chris Adolphsen of SLAC

Can we
expect higher
performance?

(At a reduced
cost?)


Nitrogen infusion

120C “modified” bake with N2 – repeatedly highest Q ever measured $>2e10$ at very high gradients >40 MV/m!




Nitrogen infusion


120C “modified” bake with N2 – repeatedly highest Q ever measured $>2e10$ at very high gradients >40 MV/m!



Not only better —but cheaper!




SRF R&D - current focus



XX% TPC → KEK/FNAL guestimate
R&D programme (until 2019)
Under resourced (NW opinion)

ILC Future (Japan)

- MEXT + JSC deliberations & critical review
 - Ongoing since 2014
 - Current focus: Human Resources
 - End in sight?
- “Green light” decision expected ~2018 (or not)
- SCRF R&D plan (‘cost reduction) now until ~2020
 - but very little resource worldwide
- Discussions and re-evaluation of energy staging
 - 250 GeV first stage
 - Looking for ~40% cost reduction over TDR price!




Final Comments

- It's been a long road...
- TESLA technology is now mature and industrialised
 - almost 'off the shelf' (cf LCLS-II)
- Performance is very close to ILC requirements
 - But not the cost!
 - Larger scale industrialisation will help if planned correctly
- New SRF 'breakthroughs' may bring significant cost benefits
 - higher gradients, higher quality factors
 - but it's industrial yield that matters
- Clearly strong interest in Japan in hosting ILC as an international project
 - But reducing the (TDR) cost is a clear priority
 - Staged energy approach being active promoted
 - Situation should clarify itself by end of 2018


Thank you for your attention 😊

Accelerator Module Test Facility (AMTF) at DESY




Purpose built infrastructure: 8 cavity acceptance tests / week
1 cryomodule test / week

Accelerator Module Test Facility (AMTF) at DESY



Purpose built infrastructure: **8 cavity acceptance tests / week**
1 cryomodule test / week

Accelerator Module Test Facility (AMTF) at DESY



Purpose built infrastructure: 8 cavity acceptance tests / week
1 cryomodule test / week

Historical performance comparison

